



Public Works Department

390 Towne Centre Dr. – Lathrop, CA 95330

Phone (209) 941-7430 – fax (209) 941-7449

www.ci.lathrop.ca.us

ADDENDUM NO. 3 – July 29, 2024

McKinley Avenue Pavement Rehabilitation Project

CIP PS 23-18

This addendum amends the Contract Drawings and Specifications for this project as follows:

1. Revised Bid Schedule with changes marked in red – See page 2 of this Addendum

Revised Bid Schedule

Bid Item	Description	Quantity	Units	Unit Price	Extended Price
1	Mobilization / Bonds / Insurance	1	LS		
2	Traffic Control	1	LS		
3	Erosion and Sediment Control Plan (ESCP)	1	LS		
4	Grind Out 13" of Existing Surface	5,320	CY		
5	Place New HMA @ 6" Depth	4,930	TON		
6	Place 7" Class 2 Aggregate Base	4,865	TON		
7	Shoulder Backing	490	TON		
8	Install Tensar NX750 Geogrid	132,500	SF		
9	Install (2) 2" Conduit	4,625	LF		
10	Install B-36 Pull Box	10	EA		
11	Thermoplastic Striping -Caltrans Std. Pln. A20, Detail 5	3,015	LF		
12	Thermoplastic Striping -Caltrans Std. Pln. A20, Detail 19	710	LF		
13	Thermoplastic Striping -Caltrans Std. Pln. A20, Detail 22	685	LF		
14	Thermoplastic Striping -Caltrans Std. Pln. A20, Detail 27B	8,820	LF		
15	Install Blue RPM's @ Fire Hydrant	2	EA		
16	Install New Signs	22	EA		
TOTAL BID:					
Total Bid Amount In Words:					

When submitting the bid for the project, the Contractor must acknowledge receipt of the addendum.

Recommended by: Ken Reed 7-29-2024
Ken Reed Date
Senior Construction Manager

Approved by: Brad Taylor 7/29/2024
Brad Taylor, P.E. Date
City Engineer